

PASCHIMANCHAL VIDYUT VITRAN NIGAM LIMITED
ELECTRICITY DISTRIBUTION DIVISION, MODINAGAR

TECHNICAL SPECIFICATION, RATE SECHDULE QUANTITY OF WORK

NAME OF WORK :- विद्युत वितरण खण्ड, मोदीनगर के अधीन विद्युत वितरण उपखण्ड-तृतीय, मोदीनगर के अन्तर्गत महामाया मन्दिर, सीकरी मेले के पर्व पर विद्युत आपूर्ति सूचारु रखने एवं मेले में विद्युत व्यवस्था के रख-रखाव को बनाये रखने का कार्य।

Tender No...../W/EDD-Modinagar/2021-22

Due Date

S. No	Name of Item	Qty.	Rate	Amount
1	Safe Cartage of PCC 8/5 mtr long from store center modinagar/J.E Store/any other place to Site of work including loading and unloading at both end. A. PCC pole 8/5 Mtr long.	08 No		
2	Cartage of line material from store center modinagar/J.E Store/any other place to Site of work including loading and unloading at both end.	10 Qtl.		
3	Errection and grouting of single including fabrication and fixing of all fitting of Pcc/S.T pole. A. Single support Pcc 8/5 Mtr/S.T pole 11 Mtr long . B. C. Grouting of support.	08 No 08 No		
4	Earthing of each support with connecting G.I wire from earth rod to support.	03 No		
5	Dismantling of damage/broken wooden cross arm and replacement with new cross arm 11 Kv/L.T Line.	03 No		
6	Laying, lifting and final sagging, binding and jumpring etc of following conductor in 11 Kv/L.T line. required for proper complication of work. A. ACSR Weasel/Dog conductor. B. L.T ABC 3x120mm ² .	1100 Mtr 80 Mtr		
7	Replacement/Repair of jumpers at both site of T/F 250/400 KVA with L.T PVC Cable including opening the binding and re-binding the same.	02 Job		
8	Dismantling and removal of broken/damage/rusted of PCc 8/5 Mtr long with removing of all fitting and re-fixing the same required for proper complication of work.	02 No		
9	Dismantling and removing of damage conductor/L.T Abc from exciting 11 Kv/L.T line and making bundling etc. A. Old and rusted damage L.T ABC. B. Old and rusted ACSR Weasal Conductor.	70 Mtr 1300 Mtr		
10	Making of Guarding above 11 kv line including fabrication and fixing of all fitting.	05 Span		
11	Resagging, retightening and rebinding of loose 11 Kv/L.T line of diffrent type ACSR Conductor/L.T ABC. A. 11 Kv line with ACSR Conductor Diffrent size. B. L.T line with L.T ABC different size.	50 Span 20 Span		
12	Straightening of tilted Pcc/S.T/R.S Joist/Rail pole with removing of all fitting and conductor and refixing the same.	05 No		
13	Re-grouting of stay set and re nozzling of stay wire including opening the binding and rebinding the same.	03 No		
14	Wrapping of polo thin around S.T pole 6 feet height including providing of all material.	100 No		
15	Temporary Bamboo fancing around 250/400 Kva T/F for safety purpose including providing of all material.	03 No		
16	Providing and fixing of M.S Clamp with nut and bolt all different capacity as per specification.	36 No		

Terms & Conditions.

1. The Service Tax if legally applicable shall be payable extra.
2. All T & P and labour shall be arrange by the contractor.
3. Old Scrap detained by the contractor.
4. Total Amount/Quantity my very+ 25 %
5. All Material arrange by the department free of cost.


Executive Engineer