

कार्यालय
अधीक्षण अभियन्ता
विद्युत जानपद वितरण मण्डल
पश्चिमोच्चल विद्युत वितरण निगम लि०
विक्टोरिया पार्क, मेरठ-250001
CIN : U31200UP2003SGC027458
E-Mail id: secivilpvvn@gmail.com
09193330145



Office of the
Superintending Engineer
Electricity Civil Distribution Circle
Paschimanchal Vidyut Vitran Nigam Ltd.
Victoria Park Meerut-250001
CIN : U31200UP2003SGC027458
E-Mail id: secivilpvvn@gmail.com
09193330145
GST NO : 09AAECP5610N1Z4


OTHER TERMS AND CONDITIONS

1. The tenders are required to read the tender documents carefully and go through the estimated rates before quoting.
2. Bill of quantity is indicative of nature of work and may not indicate all operation but contractor has to carry out all the operation as per direction of Engineer-in-charge and as per U.P.P.W.D./PVVNL/I.S./B.I.S. specification required for proper completion of the work.
3. In BOQ, quantities of individual items are approximate and may vary up to any extent as per the requirement of the site conditions; Overall variation in BOQ amount is limited to $\pm 25\%$ as per clause 10 of special condition of tender documents.
4. Before uploading the offer, the tenderer is supposed to inspect the site of work and get acquainted himself regarding site condition/problem and facilities. No compensation shall be admissible to the successful tenderer on account of the site condition.
5. Validity of this tender is 120 Days (One hundred twenty only) from the date of opening of the Part-II.
6. The work may be divided amongst more than one tenderer or only a part of work may be awarded to the successful tenderer at the discretion of the undersigned.
7. All above work shall be executed as per U.P.P.W.D./U.P.P.C.L./Relevant I.S. Code/B.I.S. specification or as per direction of E/I. In this regard the Contractor must submit the MTC Certificate of the construction materials being used at site from any recognized Institute/Lab etc as per direction of Engineer Incharge. There will no extra Payment provided to the contractor for testing of constructional materials.
8. All Electrification material/fittings/and materials of door/windows including fitting etc. shall be got approved from E/I before fixing the same at site of work.
9. Cement shall be arranged by the contractor on his own cost, fresh cement conforming to relevant I.S. of brands such as J.K. BIRLA UTTAM, ACC, AMBUJA or equivalent of major plants shall be used in the work. Contractor shall make proper storage arrangement of cement at site of work to the satisfaction of E/I. cement should always be stored in such a manner to be easily accessible of proper inspection and in a suitable weather tight building or storage shed to protect the cement from dampness.
10. TMT Steel shall be of minimum Fe 415 grade of approved make by E/I.
11. ACE Acrylic distemper and paint etc. shall be of ASIAN/BERGER/J&N Brand of approved quality which shall be got approved before using in the work from the E/I.
12. Flush doors and other fitting Aluminium fitting etc. shall be got approved by E/I flush door shutters shall be 100% waterproof ISI marked.
13. If specifications for any item of work are not covered by any of the documents mentioned in the contract the same shall be decided and conveyed by the E/I to the contractor.
14. Old bricks, if any shall be recovered from dismantling of brick work in cement/lime mortar as follows:-
 - (a) 60% of the total quantity of dismantling brick work shall be treated as received and shall be reused @ Rs. 4200.00 per 1000 in relevant item of old B/W.
 - (b) 25% of the total quantity of dismantling brick work shall be treated as bricks bats and shall be recovered @ Rs. 850.00 per Cum at site and balance shall be treated as malba.
15. Old and dismantled doors and windows if any shall be property of contractor which shall be recovered @ Rs. 200.00 per Sqm. From the contractor.
16. Old unusable steel/scrape if any of R.C.C./R.B. Work shall be recovered @ Rs. 24.00 per kg from the contractor.
17. The rates are exclusive of GST, so the quoted Rate by the Contractor is treated as GST extra. GST shall be paid by department as per prevailing law. For reimbursement of GST, The Contractor must be registered with GST Department.
18. Labour cess shall be deducted from the contractor bill as per current prevailing law.
19. 2% TDS (GST) shall be deducted as per prevailing law of the Government from the contractor bill.

U
E. V. R. KANSHAL
S.E. (C.E.), MEERUT
SAP ID-12000005

Continu.....

20. Firefighting woks, Electrical works and architecture consultancy work etc associated work shall have been done by the contractor with legal and proper licence person.
21. The rate quoted by firm shall be mentioned in this BOQ for any item is fixed for all floor/height. No extra payment shall be done due to Height for any items in this BOQ/Extra items. Variable rate shall not be acceptable and liable to be rejected.
22. The rate mentioned in this BOQ for any item is also include with shuttering, scaffolding etc. No extra payment shall be done shuttering, scaffolding etc for any items of the BOQ/Extra Items.
23. According to G.O. No. 622/23-12-2012-2 audit/08, TC dated : 08.06.2012 Additional performance guarantee shall be deposited by the tenderer in case the quoted rates are below than the departmental estimated rates i.e. 1% to 10% (0.5% per 1%) and for above 10% (1% per 1% BELOW QUOTED RATES). The Additional performance guarantee must be deposited by the tenderer at the time of agreement. If the tenderer failed to deposited additional P.G. Money at the time of agreement, then work order/agreement may be terminated & earnest money can be be forfeited.
24. No interest shall be payable on delayed payments of Contractors for running and final bills. In this regard no claim of the Contractor shall be accepted.
25. No interest shall be paid on Earnest money, Security money and tender cost fee deposited by the bidder, Tender cost fee is non refundable. Earnest money and Security money of successful bidder will be refunded after completion of work as per terms & condition.
26. The contractor will be responsible to obtain the Electrical safety NOC from the concern department within definite time period. The reimbursement of fee will be done by the department (if required).
27. Before start of the New Construction Work, It will be responsible of the contractor to obtain the fire NOC from the concern department within definite time period. The reimbursement of fee will be done by the department (if required).
28. Before start of the New Type of Construction Work, It will be responsible of the contractor to obtain the Structural drawing approval from any Govt. Recognised Technical Institute or S.E Civil within definite time period. The reimbursement of fee will be done by the department (if required).
29. Before start of the New Construction Work, It will be responsible of the contractor to obtain the Architectural drawing approval from the concern District Development authority within definite time period. The reimbursement of fee will be done by the department (if required).
30. Before start of the Earthfilling work at any site as per tender terms and condition, it is the responsibility of contractor to take perior permission of the concern district authority. Department will not be responsible.
31. It shall be the responsibility of the Engineer In-charge that means Executive Engineer (Civil), Electricity Civil Distribution Division, Meerut to take the perior approval from Engineer of Contract that means Superintending Engineer (Civil), Electricity Civil Distribution Circle, Meerut that the all Scope of work has been successfully completed assigned under the agreement within terms and condition before accepting the final bill of the contracted work. The final Certificate of completion of work shall be given by the Engineer of Contract.
32. Other terms and conditions are same attached in enclosed tender documents.


 13/02/2014
 E. V. P. KAUL
 SUPERINTENDING ENGINEER
 SAP ID-12000055