

Estimate																						
Name of the work:																						
S.N.	Items	Unit	New 250 KVA T/f Village Near Balagiri Mandir, Village-Sadarpur	New 250 KVA T/f Near Som Bazar, Peer Wali Gali Village-Sadarpur	New 250 KVA T/f Near Maszid, Sadarpur Colony,	New 250 KVA T/f Near G-86, Green Belt, Sec-44, Noida	New 250 KVA T/f Near Primary School, Vill-Asgarpur	New 250 KVA T/f Near Johad Bakhtawarpur , Noida	New 250 KVA T/f Near FNG, Vill-Shadra	New 250 KVA T/f Near Sarai Rasta, Vill-Sadarpur	New 250 KVA T/f Near Gali No-2, Vill-Chhalera	New 250 KVA T/f Near Phire Singh House, Vill-Kondli Bangar	250 To 400 KVA D-150, Sec-06 (Old)	250 To 400 KVA Sec-168	160 To 250 KVA Near Shanti Internationa l School	250 To 400 KVA Sec-15 (Bhangwal i Gali)	250 To 400 KVA Sec-15 Near-E-15,	250 To 400 KVA Sec-15 Near-G-9/15,	New 250 KVA T/F Near-A-728, Sec-19	New 400 KVA T/F Near Vill-Raipur	New 400 KVA T/F Near AKC Software Co. Vill-Raipur	New 400 KVA T/F Near AKC Highway Chapprol
			Quantity																			
1	STP 11 Mtr Long GI Bottam	Nos.	2	2	2	2	2	2	2	2	2	2	0	0	0	0	0	0	2	0	0	0
2	8.5 Mtr. Long PCC Pole	Nos.	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		2	2	2
3	MS Channel (Dropper) 100x50x2028 mm	Nos.	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0	1	2	2	2
4	ACSR Dog Conductor	Mtr.	50	50	50	50	50	50	50	50	50	50	0	0	0	0	0	0	50	50	50	50
5	ACSR Weasle Conductor	Mtr.	30	30	30	30	30	30	30	30	30	30	0	0	0	0	0	0	30	50	50	50
6	Stone Pad 300x300x75 mm	Nos.	2	2	2	2	2	2	2	2	2	2	0	0	0	0	0	0	2	2	2	2
7	Clamps for LT (T-off) with bolts & nuts	Nos.	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0	1	1	1	1
8	Holding Clamps for Top Channel TPMO & Fuse Set etc with bolts and nuts	Nos.	12	12	12	12	12	12	12	12	12	12	0	0	0	0	0	0	12	12	12	12
9	MS Top Channel (125x65x2240 mm)	Nos.	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0	1	1	1	1
10	11 KV Disc Insulator T & C type 45 KN	Nos.	6	6	6	6	6	6	6	6	6	6	0	0	0	0	0	0	6	6	6	6
11	11 Disc Fitting	Nos.	6	6	6	6	6	6	6	6	6	6	0	0	0	0	0	0	6	6	6	6
12	MS Chanel 125x65x1300 mm (T-off)	Nos.	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0	1	1	1	1
13	11 KV Poly Pin Insulator	Nos.	9	9	9	9	9	9	9	9	9	9	0	0	0	0	0	0	9	9	9	9
14	11/0.4 KV T/F 250 KVA	Nos.	1	1	1	1	1	1	1	1	1	1	0	0	1	0	0	0	1	0	0	0
15	LT ACB 400 Amp	Nos.	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0
16	11 KV Fuse Set	Nos.	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0	1	1	1	1
17	LT PVC Cable Al 3.5x240 sqmm	Mtr.	15	15	15	15	15	15	15	15	15	15	0	0	0	0	0	0	15	15	15	15
18	Al Leg Long Barrel, Off Size (LS)	Nos.	24	24	24	24	24	24	24	24	24	24	0	0	0	0	0	0	24	24	24	24
19	Danger Board barbed wire including jumper	Nos.	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0	1	1	1	1
20	Stay complete (Stay rod 16x1800 mm, Stay Wire 5 Kg., Stay Clamp, bolt & nut with grouting)	Nos.	2	2	2	2	2	2	2	2	2	2	0	0	0	0	0	0	2	2	2	2
21	Concreting of Poles (0.880 Cu.m. each)	Nos.	2	2	2	2	2	2	2	2	2	2	0	0	0	0	0	0	2	2	2	2
22	Earthing of Pole by MS Earthing rod of 20x2500 mm & 6SWG earthing wire etc.	Nos.	2	2	2	2	2	2	2	2	2	2	0	0	0	0	0	0	2	2	2	2
23	Red Oxide Paint	Ltr.	2	2	2	2	2	2	2	2	2	2	0	0	0	0	0	0	2	2	2	2
24	Aluminium Paint	Ltr.	2	2	2	2	2	2	2	2	2	2	0	0	0	0	0	0	2	2	2	2
25	Plinth for Size 2x2x1.5cm	Nos.	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0	1	1	1	1
26	400 KVA 11/0.4 KV New Transformer	Nos.	0	0	0	0	0	0	0	0	0	0	1	1	0	1	1	1	0	1	1	1
27	LT Cable 1x400 Sqmm	Mtr.	0	0	0	0	0	0	0	0	0	0	20	0	0	20	20	20	0	0	0	0
28	DISMENTALING OF T/F 250 - 5												1	1	0	1	1	1				
29	160KVA -1														1							