

Tender Inviting Authority: Superintending Engineer Electricity Civil Distribution Circle, PVVNL, Meerut.

Name of Work: Dismantling & Reconstruction of Old slab and other Misc. Civil work for Office at Electricity workshop Division, Victoria Park, Meerut.

T.S. No: 17/ECDC/MRT/2021-22

Name of the Bidder/
Bidding Firm / Company

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only.)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc from Dalla, Jhansi or other quarries in proportion 1:1.5:3 in slab, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.24	12.15	Cum	9275.00	112691.25	INR One Lakh Twelve Thousand Six Hundred & Ninety One and Paise Twenty Five Only
2	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc from Dalla, Jhansi or other quarries in proportion 1:1.5:3 in lighter beams i.e. having span upto 6m, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.25	1.88	Cum	10037.00	18869.56	INR Eighteen Thousand Eight Hundred & Sixty Nine and Paise Fifty Six Only
3	RCC work with cement, approved coarse sand (F.M. 1.8 to 2.5) and 2 cm gauge graded approved hard stone ballast like granite, quartzite etc from Dalla, Jhansi or other quarries in proportion 1:1.5:3 in RCC T beam-slab and column, excluding supply of reinforcement & its bending but including its fixing and binding the same with binding wire, including cost of all other materials labour and T&P. CSI No. 5.29	1.85	Cum	10189.00	18849.65	INR Eighteen Thousand Eight Hundred & Forty Nine and Paise Sixty Five Only
4	Precast cement concrete door sills, chaukhats boundary posts, shelves and similar small work with cement approved coarse sand (F.M. 1.5 to 2.0) and 2 cm gauge graded approved hard stone ballast in the proportion 1:1.2, excluding reinforcement but including fixing the same in position including cost of all other material, labor and T&P. CSI No. 5.33	0.50	Cum	9287.00	4643.50	INR Four Thousand Six Hundred & Forty Three and Paise Fifty Only
5	1st class brick (not less than class 150) work in 1:6 C.M. with cement and coarse sand (2.9 to 3.2 F.M) mortar in extra labour in super structure including necessary cutting and moulding of bricks as required and also including honeycomb brick work, thickness. CSI No. 6.01+6.07	0.88	Cum	4873.00	4288.24	INR Four Thousand Two Hundred & Eighty Eight and Paise Twenty Four Only
6	1st class brick work in 1:6 C.M. with cement and coarse sand of 2:25 F.M. mortar in super structure including necessary cutting and moulding of brick as required including honey comb brick work, thickness of wall one brick (230mm) thick in super structure. CSI No. 6.01+6.08	0.65	Cum	4820.00	3133.00	INR Three Thousand One Hundred & Thirty Three Only
7	Same as item no. 06 above but for wall of half brick 4.5" (115 mm) thick but in 1:6 C.M. with cement and coarse sand of 2:25 F.M. mortar. CSI No. 6.01+6.09	0.48	Cum	4971.00	2386.08	INR Two Thousand Three Hundred & Eighty Six and Paise Eight Only
8	C.P. Teak wood wrought framed and fixed including simple, mouldings straight work as in Chaukhats including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 8.01	0.05	Cum	103923.00	5196.15	INR Five Thousand One Hundred & Ninety Six and Paise Fifteen Only

J.E


S.D.O.-I


A.E

E.E


Superintending Engineer
Electy. Civil Distn. Circle
Victoria Park, Meerut (U.P.)

	Supply and fixing of 4.0 cm. thick Shisham wood part paneled and part glazed door and window shutter including supply and fixing of wooden cleats and stoppers and including fixing and adjustment of hinges bolts, locks, handles, springs and/or other fittings but excluding their supply and including fixing the glass panes with putty and necessary screws (Glass panes to be 4 mm thick.) CSI No. 8.19	1.20	Sqm	3671.00	4405.20	INR Four Thousand Four Hundred & Five and Paise Twenty Only
10	Supply and fixing Stainless Steel mosquito proof heavy quality iron wire mesh of 15x28 G over windows and including supply of Shisham wood battens (40x15) mm size and including supply and fixing of necessary screws all materials, labour and T&P etc. required for proper completion of the work. CSI No. 8.43	9.20	Sqm	1058.00	9733.60	INR Nine Thousand Seven Hundred & Thirty Three and Paise Sixty Only
11	Supply and fixing of 32 mm thick single leaf flush door shutter (boiled water resistance, phenol maldehyde resin bonded, hot pressed factory made) commercial quality to I S 2202 part-1 (1983) ISI marked including fixing of wooden cleats and stoppers and including fixing and adjustment of hinges, bolts, locks, handles, springs and other fittings but excluding their supply including all materials, labour & T&P etc. required for proper completion of work. CSI No. 8.57	2.10	Sqm	1915.00	4021.50	INR Four Thousand & Twenty One and Paise Fifty Only
12	Mild Steel or Iron work in heavy sizes such as trusses built up gates, door frames, record, racks roof work gates etc. wrought to required form including holes riveting or welding where necessary and also fixing in proper position and alignment including cost of all materials supplied by contractor. CSI No. 9.01	0.05	M.T.	83076.00	4153.80	INR Four Thousand One Hundred & Fifty Three and Paise Eighty Only
13	TMT/ Tor steel in plain work such as reinforced concrete or reinforced brick work (when not included in an over all rates) wrought to required shape as necessary including bending for proper completion of the work and including supply of steel its wastage, bend, hooks and authorized overlapping shall be measured. (Steel shall be arranged by the contractor). CSI No. 9.03	1.98	M.T.	74620.00	147747.60	INR One Lakh Forty Seven Thousand Seven Hundred & Forty Seven and Paise Sixty Only
14	12 mm thick plaster with cement mortar consisting of one part of cement & four part of coarse sand (1:4), minimum thickness not to be less than 10 mm including supply of all material, labour and T&P etc for proper completion of work. CSI No. 11.07	52.00	Sqm	178.00	9256.00	INR Nine Thousand Two Hundred & Fifty Six Only
15	Add for extra labour and materials for plaster over rough face of one brick thick wall. CSI No. 11.12	20.00	Sqm	24.00	480.00	INR Four Hundred & Eighty Only
16	S/mixing approved water proofing compound (CICO, DR FIXIT etc) in cement mortar in plaster or concrete work in the proportion as recommended by the manufacturer. CSI No. 11.15	5.00	Kg	47.00	235.00	INR Two Hundred & Thirty Five Only
17	40 cm thick 1:2:4 plain cement concrete floor with cement, approved coarse sand & 2cm graded approved stone ballast laid in panels finished with 3mm floating coat of neat cement or cement and marble dust in ratio of 5:1 as specified and removing any overlapping mortar at the joints of the panels if any and giving them a uniform finish including supply of all materials, labour and T&P etc. required for proper completion of the work. without base CC. CSI No. 12.04	22.30	Sqm	386.00	8507.80	INR Eight Thousand Six Hundred & Seven and Paise Eighty Only
18	Providing and fixing glass strips of 3.15 mm thickness & 40mm depth in joints of floor and skirting at the time of laying floors, flush with floor level including supply of all materials, labour & T&P etc. required for proper completion of work. CSI No. 12.14	55.00	RM	31.00	1705.00	INR One Thousand Seven Hundred & Five Only
19	S/F 10mm thick Group 25 acid resisting tiles of "Somany" or equivalent approved make in flooring or skirting (confirming to I.S. 4457 - 1967) in ordinary Portland cement and coarse sand in ratio 1:3 with the joints filled with acid resistant cement "Accocide" of A.C.C. or equivalent make acid resistant cement and liquid supplied with cement, mixed in 1:3 ratio to make a workable paste in G.I. Tray. The joints should be kept as 5mm and to be cured for 7 days with dilute HCL (One part acid and three parts of water). Rate should be including the cost of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 12.22	20.00	Sqm	1329.00	26580.00	INR Twenty Six Thousand Five Hundred & Eighty Only



J.E



SDO


A.E


E.E


20	Painting or varnishing new iron work in small areas or new wood work with one coat of ready mixed priming paint and one coat of approved superior quality ready mix paint "Luxol" or equivalent brand or varnish including supply of all materials, labour and T&P etc. required for proper completion of the work. Paint to be used should conform to the I.S. 103-1950. CSI No. 13.01	45.00	Sqm	71.00	3195.00	INR Three Thousand One Hundred & Ninety Five Only
21	Same as item No. 20 above but for every coat after 1st coat. CSI No. 13.02	38.30	Sqm	35.00	1340.50	INR One Thousand Three Hundred & Forty
22	Same as item No. 20 above but every coat on previously painted old wood or steel work. CSI No. 13.03	38.30	Sqm	47.00	1800.10	INR One Thousand Eight Hundred and Paise Ten Only
23	One priming coat and one coat oil bound distemper on new work including supply of all materials, labour and T&P etc. required for proper completion of the work. CSI No. 13.08	63.30	Sqm	65.00	4114.50	INR Four Thousand One Hundred & Fourteen and Paise Fifty Only
24	Same as item No. 23 above but for every coat after the first coat. CSI No. 13.09	220.70	Sqm	27.00	5958.90	INR Five Thousand Nine Hundred & Fifty Eight and Paise Ninety Only
25	Same as item No. 23 above but for every coat on previously old distempred surface. CSI No. 13.10	220.70	Sqm	33.00	7283.10	INR Seven Thousand Two Hundred & Eighty Three and Paise Ten Only
26	Applying Birla or equivalent putty on new interior or exterior surface over one coat of water based cement primer of ICI or equivalent brand for smoothening and levelling of the surface as per requirement and direction of Engineer I/C including cost of all material, labour, T & P etc required for proper completion of work. CSI No. 13.20	63.60	Sqm	84.00	5342.40	INR Five Thousand Three Hundred & Forty Two and Paise Forty Only
27	Applying BIRLA PUTTY or equivalent putty on previously bila putty smoothen surface over one coat of water base cement primer of ICI or equivalent brand for smoothening and leveling of the surface as per requirement and direction of E/I including cost of all material, labour and T&P required for proper completion of work. CSI No. 13.21	220.70	Sqm	41.00	9048.70	INR Nine Thousand & Forty Eight and Paise Seventy Only
28	Dismantling brick work or stone work in lime or cement mortar and including stacking of materials as directed by the Engineer-in-charge within a distance of 60 metres. CSI No. 15.01	13.80	Cum	505.00	6969.00	INR Six Thousand Nine Hundred & Sixty Nine Only
29	Dismantling reinforced cement concrete or reinforced brick work, including stacking of dismantled materials as directed by the Engineer-In-charge within a distance of 60 metres. CSI No. 15.03	24.00	Cum	1128.00	27072.00	INR Twenty Seven Thousand & Seventy Two Only
30	Scrapping old white or colour wash or distemper including disposal of refuse as directed by the Engineer-I/C within a distance of 60 M. CSI No. 15.12	220.70	Sqm	13.00	2869.10	INR Two Thousand Eight Hundred & Sixty Nine and Paise Ten Only
Total in Figures					461976.23	INR Four Lakh Sixty One Thousand Nine Hundred & Seventy Six and Paise Twenty Three Only
Quoted Rate in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	


J.E


S.D.O.-I


A.E


E.E


S.E

Superintending Engineer
Electy. Civil Distn. Circle
Victoria Road, Meerut (U.P.)