

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण मण्डल-द्वितीय, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान 2024-25 मद में सेमी-टर्नकी के अघार पर 11/0.4 केवी उपकेन्द्रों का निर्माण एवं क्षमतावृद्धि आदि कार्य ई-निविदा द्वारा बाह्य एजेंसी के माध्यम से कराने हेतु।

Contract No: 0120 2607114

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable								
NAME OF THE BIDDER	PRICE SCHEDULE FOR Re-TENDER NO-28/W/2023-24/EUDC-2/GZB							
NUMBER	TEXT #	NUMBE	TEXT	TEXT #	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantit y	Units	Quoted Currency In INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	
1.00	विद्युत नगरीय वितरण मण्डल-द्वितीय, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान 2024-25 मद में सेमी-टर्नकी के अघार पर 11/0.4 केवी उपकेन्द्रों का निर्माण एवं क्षमतावृद्धि आदि कार्य ई-निविदा द्वारा बाह्य एजेंसी के माध्यम से कराने हेतु।							
1.01	Construction of plinth of size 2MX2MX1.5M above ground level and one ft. below the ground level of 9". After excavation of 4" earth, brick ballast shall be provided and rammering will be done properly after that a retaining wall of 9" width by first class brick in ratio 1:4 of cement and sand shall be made. The earth shall be filled upto one ft. below the top of the plinth. After this brick ballast shall be provided upto 6" from the earth level and proper rammering shall be done. One no. jaal of 12mm MS Tor shall be fixed in the hollow of the plinth and one ft. thick RCC in 1:2:4 ratio of cement, sand and stone ballast shall be laid on the top of the plinth. The 12mm thick plastering shall be done all around the plinth in ratio 1:4 ratio of cement and sand. The contractor shall be responsible to complete the work as per direction of supervising Engineer. It includes the cost of labour, T&P, carrier etc. required for proper completion of the work (This material will be provided by the Contactor).	38	No.	INR		0.00	INR Zero Only	
1.02	Fabrication of wire mesh fencing frames of different size fabricate out of MS angle iron of size 3x3x2 Meter. Each frame duly welded and fixing with wire mesh of size 25x25x10 SWG hot dipped galvanized iron within the frame pressed under MS flats of size 40x5mm inside the angle on all four side with help of approx. 20No. Bolts & Nuts of 10mm diameter 45cm legs of frame will be grouted in 1:2:4 cement coarse sand and 20mm gauge stone blast in the size of 0.22x0.22x0.45meter. Each will be painted with one coat of red oxide and two coat of Alluminium paint of approved mark after proper cleaning. Fixing of wire mess fencing around on plinth of T/F with wire gauge 25x25mm, MS Angle 35x35x5mm with gate.	36	Mtr.	INR		0.00	INR Zero Only	
1.03	Safe Carriage of 69 No. ST Pole 11 Mtrs. Long, 6 No. ST Pole 9 Meter Long & 114 No. PCC Pole 8.5 Meter Long from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	189	No.	INR		0.00	INR Zero Only	
1.04	Safe Carriage of 01 No. 100 KVA Transformer & 36 No. 250 KVA Transformer from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	37	No.	INR		0.00	INR Zero Only	
1.05	Carriage of LT XPLE Cable 1x240 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	1545	Mtr.	INR		0.00	INR Zero Only	
1.06	Carriage of LT XPLE Cable 1x400 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	1315	Mtr.	INR		0.00	INR Zero Only	
1.07	Carriage of ALL XPLE Cable 3.5x240 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	36	Mtr.	INR		0.00	INR Zero Only	
1.08	Carriage of LT ABC Cable 3x120+1x95+1x16 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	6047	Mtr.	INR		0.00	INR Zero Only	
1.09	Carriage of HT XLPE 11 KV Cable 3x120 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	450	Mtr.	INR		0.00	INR Zero Only	
2.00	Carriage of ACSR Dog Conductor from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	11940	Mtr.	INR		0.00	INR Zero Only	
2.01	Carriage of ACSR Weasel Conductor from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	850	Mtr.	INR		0.00	INR Zero Only	
2.02	Carriage of line accessories such as 04 No. Cable Box O/D 11 KV 3x120 Sq.mm., 450 Meter LT XPLE Cable 1x35 Sq.mm., 315 No. 11 KV Composite Polymeric PIN Insulator, 87 No. 11 KV Composite Polymeric Disc Insulator, 300 No. LT Shackle Insulator with clamp, 35 No. DO Fuse Set 11 KV and 40 No. Earth Rod (2540x20mm), 07 No. LT TVM Meter 5A and 50 No. Disc Fitting 45KN from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only	
2.03	Installation of 100 KVA Transformer. Complete work as per requirement of site & as per RESPO norms.	1	No.	INR		0.00	INR Zero Only	
2.04	Installation of 250 KVA Transformer. Complete work as per requirement of site & as per RESPO norms.	36	No.	INR		0.00	INR Zero Only	
2.05	Erection, Grouting, concreting & Installation of Double Pole Structure Including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	34	No.	INR		0.00	INR Zero Only	
2.06	Erection, Grouting, concreting & Installation of Single Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	1	No.	INR		0.00	INR Zero Only	
2.07	Earthing work of pole. Complete work as per requirement of site and as per RESPO Norms.	8	No.	INR		0.00	INR Zero Only	
2.08	Laying of LT XPLE Cable 1x240 Sq.mm. Proper completion of work as per requirement of site and as per RESPO Norms.	1300	Mtr.	INR		0.00	INR Zero Only	
2.09	Laying of LT XPLE Cable 1x400 Sq.mm. Proper completion of work as per requirement of site and as per RESPO Norms.	1150	Mtr.	INR		0.00	INR Zero Only	
3.00	Laying of LT XPLE Cable 3.5x240 Sq mm. Proper completion of work as per requirement of site and as per RESPO Norms.	30	Mtr.	INR		0.00	INR Zero Only	

3.01	Laying of LT AB Cable 3x120+1x95+1x16 Sq. mm. Proper completion of work as per requirement of site and as per RESPO Norms.	5500	Mtr.	INR		0.00	INR Zero Only
3.02	Laying of HT XLPE 11 KV Cable 3x120 Sq. mm. Proper completion of work as per requirement of site and as per RESPO Norms.	380	Mtr.	INR		0.00	INR Zero Only
3.03	Laying of ACSR Dog Conductor Proper completion of work as per requirement of site and as per RESPO Norms.	8650	Mtr.	INR		0.00	INR Zero Only
3.04	Laying of ACSR Weasel Conductor Proper completion of work as per requirement of site and as per RESPO Norms.	610	Mtr.	INR		0.00	INR Zero Only
3.05	Installation of DO Fuse Set as per RESPO Norms. Complete work as per requirement of site.	35	No.	INR		0.00	INR Zero Only
3.06	Installation of LT TVM Meter 5A as per RESPO Norms. Complete work as per requirement of site.	7	No.	INR		0.00	INR Zero Only
3.07	Fixing of Cable Box O/D 11 KV 3x120 Sq. mm as per RESPO norms.	4	No.	INR		0.00	INR Zero Only
3.08	PROVIDING AND FIXING Earth Rod size 25x40x20 mm	40	No.	INR		0.00	INR Zero Only
3.09	PROVIDING AND FIXING MS Channel 100x50x5 MM.	3755	Kg.	INR		0.00	INR Zero Only
4.00	PROVIDING AND FIXING MS Channel Angle 75x75x6 MM.	90	Kg.	INR		0.00	INR Zero Only
4.01	PROVIDING AND FIXING Dangle Board with Clamp for 11 KV	3	No.	INR		0.00	INR Zero Only
4.02	PROVIDING AND FIXING G.I. Barbed Wire.	2	Kg.	INR		0.00	INR Zero Only
4.03	PROVIDING AND FIXING G.I. Wire 6 SWG.	69	Kg.	INR		0.00	INR Zero Only
4.04	PROVIDING AND FIXING G.I. Wire 8 SWG.	74	Kg.	INR		0.00	INR Zero Only
4.05	PROVIDING AND FIXING G.I. Strip of size 25x3 mm	246	Kg.	INR		0.00	INR Zero Only
4.06	PROVIDING AND FIXING G.I. Strip of size 50x6 mm for Earthing Connection of Transformer.	148	Kg.	INR		0.00	INR Zero Only
4.07	PROVIDING AND FIXING Nut & Bolt with washer off size as per RESPO.	668	Kg.	INR		0.00	INR Zero Only
4.08	PROVIDING AND FIXING ALL Crimping Lug 240 Sq. mm.	130	No.	INR		0.00	INR Zero Only
4.09	PROVIDING AND FIXING ALL Lug 70 Sq. mm.	156	No.	INR		0.00	INR Zero Only
5.00	PROVIDING AND FIXING ALL Lug 400 Sq. mm.	75	No.	INR		0.00	INR Zero Only
5.01	PROVIDING AND FIXING Copper L-Piece 400 Sq. mm. for 250 KVA TF	68	No.	INR		0.00	INR Zero Only
5.02	PROVIDING AND FIXING Tainness Fuse Unit 300 Amp. With complete fitting as per RESPO Norms.	1	No.	INR		0.00	INR Zero Only
5.03	Providing and Fixing Chemical Earthing with Terminal Hole. 8mm. Service Life-Up to 12 Years. Terminal Size 50mm x 6mm Earthing work upto 10 feet depth. 90mm	94	No.	INR		0.00	INR Zero Only
5.04	PROVIDING AND FIXING 11 KV V-Type Steel Cross Arm 65x65x6mm	22	No.	INR		0.00	INR Zero Only
5.05	PROVIDING AND FIXING P.G. Clamps.	112	No.	INR		0.00	INR Zero Only
5.06	PROVIDING AND FIXING M.S. Holding Clamps.	394	No.	INR		0.00	INR Zero Only
5.07	PROVIDING AND FIXING LT Insulating Piercing Clamps 120 Sq. mm.	368	No.	INR		0.00	INR Zero Only
5.08	PROVIDING AND FIXING LT Suspension Clamp with Eye Hook.	218	No.	INR		0.00	INR Zero Only
5.09	PROVIDING AND FIXING Dead End Clamp with Eye Hook.	126	No.	INR		0.00	INR Zero Only
6.00	PROVIDING AND FIXING Stone Pad.	35	No.	INR		0.00	INR Zero Only
6.01	PROVIDING AND FIXING LT Stay Assembly Complete.	15	No.	INR		0.00	INR Zero Only
6.02	PROVIDING AND FIXING 11 KV TPMO with Jaw and Blades. Complete the fitting as per RESPO Norms.	4	No.	INR		0.00	INR Zero Only
6.03	PROVIDING AND FIXING 450 Meter LT XPLE Cable 1x35 Sq. mm.	450	Mtr.	INR		0.00	INR Zero Only
Total in Figures							
Quoted Rate in Words							

INR Zero Only

0.00	INR 2000 Only
------	---------------