

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghazabad (UP)

Name of Work: विद्युत नगरीय वितरण खण्ड-द्वितीय, गाँव/बाराद के कोठी/न में बिज विहार व सूर्यनगर पुलिसा पर सेतु निर्माण में बावक आगोपगोपू स्थानात्तरा/स्थाना एवं लाईनों को पूर्ण जमा योजना में बाहर एजेसी के माध्यम से शिफ्ट कराना व अन्य कार्य।

Contract No: 0120 2607114

Name of the Bidder	
--------------------	--

PRICE SCHEDULE FOR E-TENDER NO-13/M/2024-25/EUDD-2/GZB

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable

NUMBER	TEXT #	Item Description	NUMBE	TEXT	TEXT #	NUMBER #	NUMBER #	TEXT #
* Sl. No.			Quantit	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	विद्युत नगरीय वितरण खण्ड-द्वितीय, गाँव/बाराद के कोठी/न में बिज विहार व सूर्यनगर पुलिसा पर सेतु निर्माण में बावक आगोपगोपू स्थानात्तरा/स्थाना एवं लाईनों को पूर्ण जमा योजना में बाहर एजेसी के माध्यम से शिफ्ट कराना व अन्य कार्य।	3	4	5	6	7	8
1.00								
1.01		Safe Carriage of HT 11 KV XLPE Cable 3x185 Sq.mm from PVVNL Store Sahibabad/ Ghazabad/ Noida to site of work including loading & unloading at both side.	1832	Mtr.	INR		0.00	INR Zero Only
1.02		Safe Carriage of HT 33 KV XLPE Cable 3x300 Sq.mm from PVVNL Store Sahibabad/ Ghazabad/ Noida to site of work including loading & unloading at both side.	2000	Mtr.	INR		0.00	INR Zero Only
1.03		Safe Carriage of Steel Tubular Pole 11 Meter from PVVNL Store Sahibabad/ Ghazabad/ Noida to site of work including loading & unloading at both side.	10	No.	INR		0.00	INR Zero Only
1.04		Safe Carriage of line accessories such as 100 meter Dog Conductor, 21 No. 33 KV Pin Insulator, 21 No. 33 KV Pin Insulator B&S type and 36 No. 33 KV Disc Fittings for Dog Conductor, 35 Meter G.I. Pipe 6 dia, 120 No. 11 KV Disc Insulator B&S Type from PVVNL Store Sahibabad/ Ghazabad/ Noida to site of work including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only
1.05		Safe Carriage of 33 KV XLPE Straight Through Cable Box 3x300 Sq.mm from PVVNL Store Sahibabad/ Ghazabad/ Noida to site of work including loading & unloading at both side and work of Filling/Installation as per RESPO.	2	No.	INR		0.00	INR Zero Only
1.06		Safe Carriage of 33 KV XLPE Outdoor Cable Box 3x300 Sq.mm from PVVNL Store Sahibabad/ Ghazabad/ Noida to site of work including loading & unloading at both side and work of Filling/Installation as per RESPO.	8	No.	INR		0.00	INR Zero Only
1.07		Safe Carriage of 11 KV XLPE Outdoor Cable Box 3x185 Sq.mm from PVVNL Store Sahibabad/ Ghazabad/ Noida to site of work including loading & unloading at both side and work of Filling/Installation as per RESPO.	14	No.	INR		0.00	INR Zero Only
1.08		Laying of 11 KV HT Cable of 3x185 Sq.mm with Trenchless method by providing of HDPE Pipe Bore 160 mm dia and proper completion of work as per requirement of site.	1612	Mtr.	INR		0.00	INR Zero Only
1.09		Laying of 33 KV HT Cable of 3x300 Sq.mm with Trenchless method by providing of HDPE Pipe Bore 160 mm dia and proper completion of work as per requirement of site.	1710	Mtr.	INR		0.00	INR Zero Only
2.00		Work of Chemical Pipe Earthing by providing all the required material (80 mm dia 3m long pipe) pas per RESPO specification.	30	Mtr.	INR		0.00	INR Zero Only
2.01		Providing and Installation of 11 KV Ring Main Unit (RMU) with all the required accessories. Complete work as per requirement of site.	2	No.	INR		0.00	INR Zero Only
2.02		Work of shifting of 3 way mounted RMU (Outdoor) Smart controlling unit with all other accessories. Complete work as per requirement of site.	1	No.	INR		0.00	INR Zero Only
2.03		Work of shifting of FRP Fencing complete with gate as per specification for RMU (size 3m x 2.4m x 2.4m). Complete work as per requirement of site.	1	No.	INR		0.00	INR Zero Only
2.04		Work of concreting of FRP Fencing supports with plinth (size 0.3 x 0.3 x 0.5) Cubic Meter x 10 Nos. each. Ration 1:3:6. Complete work as per requirement of site.	1	No.	INR		0.00	INR Zero Only
2.05		Earthing of Pole as per RESPO specification.	10	No.	INR		0.00	INR Zero Only
2.06		Providing and Fixing of MS Angle Iron 65x65x3 mm bracing with 4 clamps.	5	Set	INR		0.00	INR Zero Only
2.07		Providing and Fixing of Top Channel 125x65 mm, 3200 mm with Clamp.	5	No.	INR		0.00	INR Zero Only
2.08		Providing and fixing of Stone Pad 300x300x75 mm.	10	No.	INR		0.00	INR Zero Only
2.09		Providing and Fixing of Earth Wire Clamp with Bolt & Nut.	5	No.	INR		0.00	INR Zero Only
3.00		Providing and Fixing of NG Clamp for Dog Conductor.	60	No.	INR		0.00	INR Zero Only
3.01		Providing and Fixing of Number Plate.	5	No.	INR		0.00	INR Zero Only
3.02		Providing and Fixing of Danger Board with Clamp.	20	Kg.	INR		0.00	INR Zero Only
3.03		Providing and Fixing of Barbe Wire.	5	Kg.	INR		0.00	INR Zero Only
3.04		Providing and Fixing of Aluminum Tape.	10	Ltr.	INR		0.00	INR Zero Only
3.05		Providing and Fixing of Red Oxide Paint.	40	No.	INR		0.00	INR Zero Only
3.06		Providing and Fixing of Gray Set Complete.	15	No.	INR		0.00	INR Zero Only
3.07		Providing and Fixing of F Brackets.	40	No.	INR		0.00	INR Zero Only
3.08		Concreting of Support.	275	Kg.	INR		0.00	INR Zero Only
4.00		Concreting of Stay.	24	No.	INR		0.00	INR Zero Only
4.01		PROVINDING and FIXING G.I. Nut & Bolts.	8	No.	INR		0.00	INR Zero Only
4.02		PROVINDING and FIXING MS Clamp with Nut & Bolts.	40	No.	INR		0.00	INR Zero Only
4.03		PROVINDING and FIXING MS Dropper Channel.	4	No.	INR		0.00	INR Zero Only
4.04		PROVINDING and FIXING G.I. Flat size 50x6mm.	4	Mtr.	INR		0.00	INR Zero Only
4.05		Carriage of old & used material from site to Store Sahibabad/ Ghazabad including loading & unloading at both side.	1	Job	INR		0.00	INR Zero Only
4.06								
4.07								
4.08								
Total in Figures								
Quoted Rate in Words								