

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण खण्ड-बन्दम, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान 2024-25 (पार्ट-2) मद में 33 केवी0 लाईन का सुदृढ़ीकरण एवं आर0एम0यू0 लगाने आदि के कार्य हेतु।

Contract No: 9193320600

Name of the Bidder/								
<div>PRICE SCHEDULE FOR E-TENDER NO-22/W/2024-25/EUDD-VI/EUDC-2/GZB</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable</div>								
NUMBER	TEXT #	NUMBE	TEXT	TEXT #	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantit y	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	
1.00	विद्युत नगरीय वितरण खण्ड-बन्दम, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान 2024-25 (पार्ट-2) मद में 33 केवी0 लाईन का सुदृढ़ीकरण एवं आर0एम0यू0 लगाने आदि के कार्य हेतु।							
1.01	Safe Cartage of ST Pole 13 Meter Long SP-72 from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	12	No.	INR		0.00	INR Zero Only	
1.02	Carriage of 11 KV HT Cable 3x185 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	710	Mtr.	INR		0.00	INR Zero Only	
1.03	Carriage of ACSR Dog Conductor from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	10000	Mtr.	INR		0.00	INR Zero Only	
1.04	Carriage of line accessories such as 36 No. 33 KV Disc Insulator, 36 No. 33 KV Polymeric PIN Insulator, 12 No. Earth Rod (2540x20mm), 12 No. 33 KV V-Type Cross Arm from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only	
1.05	Carriage of material such as 36 No. 33 KV Disc Insulator, 36 No. 33 KV Polymeric PIN Insulator, 12 No. Earth Rod (2540x20mm), 12 No. 33 KV V-Type Cross Arm from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only	
1.06	Work of Concreting/Grouting of pole by providing all the required material for completion of work. Complete the work as per requirement of site/RESPO norms.	12	No.	INR		0.00	INR Zero Only	
1.07	Fixing of Outdoor Cable Box 11 KV 3x185 Sq.mm	18	No.	INR		0.00	INR Zero Only	
1.08	Laying/Erection of ACSR Dog Conductor. Proper completion of work as per requirement of site.	10000	Mtr.	INR		0.00	INR Zero Only	
1.09	Normal Laying of 11 KV HT Cable of 3x185 Sq.mm. Proper completion of work as per requirement of site.	710	Mtr.	INR		0.00	INR Zero Only	
2.00	Providing and FIXING Chemical Earthing with GI Strip.	5	No.	INR		0.00	INR Zero Only	
2.01	Providing and FIXING Water Lavel Earthing with GI Strip.	1	No.	INR		0.00	INR Zero Only	
2.02	Earthing of pole by providing Earth Rod (2540x20mm)	12	No.	INR		0.00	INR Zero Only	
2.03	PROVINDING AND FIXING MS Channel 100x50 MM.	300	Kg.	INR		0.00	INR Zero Only	
2.04	PROVIDING AND FIXING Nut & Bolt with washer off Size as per RESPO.	20	Kg.	INR		0.00	INR Zero Only	
2.05	PROVIDING AND FIXING M.S. Holding Clamps with nut & bolt.	52	No.	INR		0.00	INR Zero Only	
2.06	PROVIDING AND Instalation 11 KV RMU 3Way Phase with over current and earth fault protection	3	No.	INR		0.00	INR Zero Only	
2.07	Insttalation Plant of 11 KV RMU.	3	No.	INR		0.00	INR Zero Only	
2.08	Fancing for RMU (Fiber Make)	3	Mtr.	INR		0.00	INR Zero Only	
Total in Figures						0.00	INR Zero Only	
Quoted Rate in Words				INR Zero Only				