

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण मण्डल-द्वितीय, गाजियाबाद के अन्तर्गत विद्युत नगरीय वितरण खण्ड-षष्ठम, गाजियाबाद के कार्यक्षेत्र में यू0पी0 स्टेट रोड ट्रॉसपोर्ट कारपोरेशन, यू0पी0 रोडवेज ऑफिस साहिबाबाद पर 1740 के0वी0ए0 (विधा एल0एम0वी-11) का नया संयोजन निवेश मित्र/झटपट पोर्टल से प्राप्त पूर्ण जमा योजना मद में निर्गत करने सम्बन्धी कार्य वाह्य एजेन्सी के माध्यम से कराने हेतु।

Contract No: 9193320600

Name of the Bidder/ Bidding							
<div>PRICE SCHEDULE FOR E-TENDER NO-26/W/2024-25/D-6/EUDC-2/GZB</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable</div>							
NUMBER	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.00	विद्युत नगरीय वितरण मण्डल-द्वितीय, गाजियाबाद के अन्तर्गत विद्युत नगरीय वितरण खण्ड-षष्ठम, गाजियाबाद के कार्यक्षेत्र में यू0पी0 स्टेट रोड ट्रॉसपोर्ट कारपोरेशन, यू0पी0 रोडवेज ऑफिस साहिबाबाद पर 1740 के0वी0ए0 (विधा एल0एम0वी-11) का नया संयोजन निवेश मित्र/झटपट पोर्टल से प्राप्त पूर्ण जमा योजना मद में निर्गत करने सम्बन्धी कार्य वाह्य एजेन्सी के माध्यम से कराने हेतु।						
1.01	Safe Carriage of ST Pole 11 Meter Long from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	8	No.	INR		0.00	INR Zero Only
1.02	Safe Carriage of 11 KV HT XLPE cable (3x185 sq.mm.) from Store Centre Sahibabad/Ghaziabad/Noida to site of work including loading and unloading at both ends.	990	Mtr.	INR		0.00	INR Zero Only
1.03	Carriage of line accessories such of 02 No. 11 KV Drow Out Fuse set, 18 No. Outdoor Cable Box 11 KV 3x185 Sq.mm, 24 No. 11 KV Composite Polymer Pin Insulator & 50 No. ACSR Dog Conductor from Store Centre Sahibabd/Ghaziabad/Noida to site of work & installation including loading and unloading at both ends. Complete work as per requirement of site including all the	1	Job.	INR		0.00	INR Zero Only
1.04	Laying/Erection of ACSR Dog Conductor. Proper completion of work as per requirement of site.	50	Mtr.	INR		0.00	INR Zero Only
1.05	Normal Laying of 11 KV HT Cable of 3x185 Sq.mm. Proper completion of work as per requirement of site.	990	Mtr.	INR		0.00	INR Zero Only
1.06	Providing and FIXING Chemical Earthing with G.I. Strip as per RESPO Norms.	4	No.	INR		0.00	INR Zero Only
1.07	Concreting of Poles as per RESPO Norms.	8	No.	INR		0.00	INR Zero Only
1.08	Providing & Fixing Earth Rod 2540X20mm as per RESPO Norms.	10	No.	INR		0.00	INR Zero Only
1.09	Providing & Fixing G.I. Barbed Wire as per RESPO Norms.	10	Kg.	INR		0.00	INR Zero Only
2.00	Providing & Fixing Nut Bolt with Washar of size as per RESPO Norms.	20	Kg.	INR		0.00	INR Zero Only
2.01	Providing & Fixing Aluminium Paint as per RESPO Norms.	8	Ltr.	INR		0.00	INR Zero Only
2.02	Fixing of Outdoor Cable Box 11 KV 3x185 Sq.mm	18	No.	INR		0.00	INR Zero Only
2.03	Fixing 11 KV Drow Out Fuse set as per RESPO Norms.	2	No.	INR		0.00	INR Zero Only
2.04	Providing & Fixing MS Channel 125x65 mm as per RESPO Norms.	450	Kg.	INR		0.00	INR Zero Only
2.05	Providing & Fixing Red Oxide as per RESPO Norms.	8	Kg.	INR		0.00	INR Zero Only
2.06	Providing & Fixing MS Holding Clamps as per RESPO Norms.	45	No.	INR		0.00	INR Zero Only
2.07	Providing & Fixing G.I. Wire 6 SWG as per RESPO Norms.	20	Kg.	INR		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					